BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

NO:BBMP/EE/YNK.D/EPMT-01/2020-21 Dt:02-5-2020

APPROVED TENDER SCHEDULE –'B'

Item 43

Name of Work :-Emergency grants in ward no 03, Attur

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri B K NAGENDRA ( )	
				Rate	Rate in Words
1	KSRRB 300: Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 m and an average lift upto 0.5 m. excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (P.No-143, I.No-19.1)	Cum	630.00	230.19	Two Hundred Thirty Paise Nineteen Only
2	KSRB 2-2.1: Earthwork excavation by manual means for foundation of buildings, culverts, water supply and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. including breaking of clods complete as per specifications. No. KBS 2.1 (a) (Item No.2.3.5, Page no.6)	Cum	336.00	346.23	Three Hundred FourtySix Paise TwentyThree Only
3	Providing precast slab of 100mm tick including cost of all materials, labour, curing, transportation, loading, unloading etc,. complete as per the direction.	Sqm	378.00	2149.00	Two Thousand One Hundred FourtyNine Only
4	Providing precast slab of 250mm tick including cost of all materials, labour, curing, transportation, loading, unloading etc,. complete as per the direction.	Sqm	39.60	4984.00	Four Thousand Nine Hundred EightyFour Only

	Providing and fixing pre cast solid cement concrete kerb stones out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc., complete as per direction of Engineer incharge.(P. No-27, I. No-5.30 of PW, P&IWTD SR 2018-19)	Nos	500.00	397.00	Three Hundred NinetySeven Only
6	KSSRB 800-1: Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 P. No-180, I. No-24.1	Sqm	67.50	78.00	SeventyEight Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.